

PLUMBING FIXTURE SCHEDULE					
FIXTURE	TYPE	DESCRIPTION	WASTE	CW	HW
WC	WATER CLOSET (W/FV)	"AM STD." "MADERA" NO. 2234.015 VITREOUS CHINA ELONGATED FLOOR MTD., SIPHON JET, WITH SLOAN ROYAL 110-3 WATER SAVER FLUSH VALVE AND OLSENITE NO. 95 OPEN FRONT SEAT.	3"	1"	-
LAV	LAVATORY (WALL HUNG)	"AM. STD" NO. 0356.421 "LUCERNE" LAVATORY WITH CONTOURED SIDE AND BACK SPLASH. SHIELDS, CENTER PUNCHING, 20 x 18 VITREOUS CHINA; FURNISH OFFSET GRID DRAIN 7723.018 AND TAIL PIECE. FURNISH "DELTA" 2502 ADJUSTABLE SLOW CLOSING METERING FAUCET, WITH PUSH BUTTON ACTUATOR, PROVIDE 0.5 GPM FLOW RESTRICTOR.	1-1/4"	1/2"	1/2"
UR	URINAL	WASHBROOK VITREOUS CHINA URINAL. URINAL RATED FOR 1.0 GPF. PROVIDE SLOAN ROYAL 186 EXPOSED LEVER OPERATED FLUSH VALVE. URINAL COLOR WILL BE WHITE. MOUNT URINAL 24" FROM FINISH FLOOR TO LIP OF URINAL. PROVIDE CARRIER.	2	3/4"	-
FD	FLOOR DRAIN (GENERAL PURPOSE)	"J.R. SMITH 2005-A WITH ENAMELED CAST IRON BODY WITH FLASHING COLLAR AND ADJUSTABLE 6" ROUND NICKEL BRONZE STRAINER. PROVIDE A TRAP PRIMER CONNECTION.	3"	1/2"	-
H-1	WALL HYDRANT	WOODFORD MODEL B-24-3/4-ER WALL FAUCET WITH VACUUM BREAKER, POLY CARBONATE WHEEL HANDLE, BRASS CONSTRUCTION MOUNTED IN BRASS BOX SIZED TO BRICK COURSES, AND PROVIDED WITH LOOSE T-HANDLE.	-	3/4"	-

PLUMBING NOTES:

1. THE ENTIRE PLUMBING INSTALLATION, MATERIALS AND WORKMANSHIP SHALL COMPLY WITH THE FLORIDA PLUMBING AND BUILDING CODE 2004, ADOPTED AMENDMENTS, STATE AND LOCAL REGULATIONS AND REQUIREMENTS OF THE DEPARTMENT OF HEALTH.
2. THE ENTIRE PLUMBING INSTALLATION EQUIPMENT AND MATERIALS SHALL BE LEAD FREE.
3. ALL HANDICAPPED FIXTURES AND EQUIPMENT INSTALLATIONS SHALL MEET THE GOVERNING HANDICAPPED CODE IN ALL RESPECTS.
4. THE DRAWINGS ARE NOT INTENDED TO SHOW COMPLETE OR PRECISE DETAILS OF THE BUILDING OR INSTALLATION IN EVERY RESPECT. VERIFY AND COORDINATE ALL WORK AND EQUIPMENT LOCATIONS WITH OTHER TRADES BEFORE FABRICATION OR INSTALLATION OF THE WORK IS STARTED. COORDINATE WITH ALL REQUIREMENTS OF APPROVED EQUIPMENT TO BE FURNISHED. REPORT ALL CONFLICTS TO THE ARCHITECT BEFORE WORK IS FABRICATED AND INSTALLED.
5. ALL SANITARY PIPING INDICATED IS BELOW SLAB UNLESS NOTED OTHERWISE.
6. ALL FLOOR DRAINS SHALL HAVE DEEP SEAL TRAPS.

PLUMBING LEGEND

- PIPING & VALVES:
- NEW WORK
- EXISTING WORK TO REMAIN
- EXISTING WORK TO BE REMOVED
- COLD WATER (CW)
- HOT WATER (HW)
- HOT WATER RETURN (HWR)
- S

SANITARY (S)
- V

VENT (V)
- W

WASTE
- G

GAS
- BALL VALVE
- BUTTERFLY VALVE
- GATE VALVE
- GLOBE VALVE
- STRAINER
- PIPE UNION
- CHECK VALVE
- ASME PRESSURE/TEMPERATURE RELIEF VALVE
- PIPE UP
- PIPE DOWN

- ABBREVIATIONS & SYMBOLS:
- WALL CLEAN OUT
- FLOOR CLEAN OUT
- A/C

ABOVE CEILING
- AP

ACCESS PANEL
- B/F

BELOW FLOOR
- BFP

BACK FLOW PREVENTER
- EX.

EXISTING
- HD

HUBB DRAIN
- VTR

VENT THROUGH ROOF
- WH

WATER HEATER
- POINT OF CONNECTION - NEW WORK TO EXISTING

- PLUMBING FIXTURES:
- FD

FLOOR DRAIN
- H

WALL HYDRANT
- HB

HOSE BIBB
- LAV

LAVATORY
- P


PLUMBING FIXTURE
- S

SINK
- PDI-A



SHOCK ARRESTOR - P.P.I. SIZE
- UR

URINAL
- WC

WATER CLOSET



PARTIAL SITE PLAN
SCALE: 3/32" = 1'-0"



r. michael white
architect p.a.

1255 S.E. 10th Ave.
ocala, florida 34471
pr (352) 368-3689 f: (352) 368-3689
ar 00007860

project name:

Range Maintenance
Administration Expansion

FOR:

Department of Military Affairs
Starke, Fl.

project number: 209035

consultants:

Estrella Engineering Incorporated
1555 Kingsley Ave., Suite 302 * Orange Park, Florida 32073
(904) 269-7880 * Mail@Estrella-Engineering.com
Certificate of Authorization - EB 5020

seal / signature:

Larry Estrella, PE
License No.36242

revision item:

date:

drawn by:

RE

checked by:

LE

computer file name:

issue date:

08/18/2011

sheet title:

PARTIAL SITE PLAN,
PLUMBING SCHEDULES,
NOTES AND LEGEND

drawing scale:

SCALE AS NOTED

sheet number:

P1.1